BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

Draft Tender Schedule-B

Name of Work : Improvements of Main Roads and Cross Roads from 13th cross to 18th cross, 1st cross to 4th cross Roads & Drains in Jakkur layout in ward No. 7 Byatarayanpura, Kodigehalli sub division

Sl. No	Approved Quantity	Description	Unit	Sanctioned Rates	Rates Quoted by the Contractor	
				In Figures	Figures	In Words
1	12705.00	Removing BS Slab of drain and stacking. (P.No.28. I.No.5.32 of PW.P&IWTD S.R 2012-13)	Sqm	44.47		(46.40)
2	8893.50	Refixing stone slabs of drains and pointing in CM 1:3. (P.No.28. I.No. 5.33 of PW.P&IWTD S.R 2012-13)	Sqm	63.00		(64.85)
3	3811.50	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc.. complete. (7.50cms thick) (P.No.28. I.No.5.31.1 of PW.P&IWTD SR 2012-13)	Cum	315.36		(318.00)
4	6160.00	KSRRB M300-1: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m. excavated surface levelled and sides neatly dressed. the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3. (P.No.150 I.No.19.1 of PW.P&IWTD S.R 2012-13)	Sqm	58.32		(61.00)
5	30800.00	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour. HOM of machinery complete as per specifications. (158. I.No. 19.64 SR 2012-13)		3.78		(3.75)
6	6622.00	KSRRB M400-17. Providing. laying. spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site. laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 167. Item No. 20.18 SR-2012-13	Cum	1059.48		(1038)
7	30800.00	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 172. Item No. 21.6 SR-2012-13)	Sqm	42.83		(41.0)

P.T.O.

8	770.00	KSRRB M500-18. Provi[redacted]g semi dense bituminous concrete 25 mm thick with 100-120 [redacted]HMP producing an average output of 75 t[redacted] using crushed aggregates of specified grad[redacted]ith bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 174, Item No. 21.20.5 SR-2012-13)	Cum	9404.74		(9069)
9	1475.00	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	Cum	81.00		

Junior Engineer
Ward No.07

Assistant Executive Engineer
Kodigehalli sub division

Executive Engineer
Byatarayanapura division
BBMP, Bangalore
12/7/2013

"DTS approved"

12/7/13